

Town of Plymouth

Bid 21512 Sidewalk Construction & Rehab

March 20 ,2015 11:00 a.m.

Company	MA Hwy Pre-Qual	Bid Bond	Amount of Bid
IW Harding	x	x	\$ 1,607,550.00
LAL Construction Co Inc.	x	x	\$ 929,950.00
P.A. Landers, Inc.	x	x	\$ 1,437,906.25
Pavao Construction	x	x	\$ 1,075,050.00

Low Bidder LAL Construction Co Inc.

	Description	Est Qty	Unit	Unit Price	Total
120.1	Unclassified Excavation	1,000	CY	\$25.00	\$25,000.00
129.1	Pavement Milling (Areas 2'-4'Wide)	500	SY	\$14.00	\$7,000.00
146	Drainage Structure - Removed	10	EA	\$400.00	\$4,000.00
151.02	Gravel Borrow	1,000	TON	\$20.00	\$20,000.00
153	Controlled Density Fill - Excavatable	100	CY	\$100.00	\$10,000.00
156	Crushed Stone	100	TON	\$30.00	\$3,000.00
201	Catch Basin (4.0'Dia)	10	EA	\$2,800.00	\$28,000.00
201.1	Catch Basin (5.0' Dia)	10	EA	\$3,100.00	\$31,000.00
201.3	Catch Basin (4.0' Dia) With Leaching Top	10	EA	\$3,100.00	\$31,000.00
202	Manhole	10	EA	\$2,800.00	\$28,000.00
204	Gutter Inlet	10	EA	\$1,000.00	\$10,000.00
205.1	Leaching Basin (Including Stone & Fabric)	10	EA	\$3,800.00	\$38,000.00
220	Drainage Structure - Adjusted	10	EA	\$350.00	\$3,500.00
220.2	Drainage Structure - Rebuilt	10	FT	\$350.00	\$3,500.00
220.3	Drainage Structure - Change In Type	10	EA	\$600.00	\$6,000.00
222.3	Frame And Grate (or cover) Municipal standard	10	EA	\$700.00	\$7,000.00
222.4	Double Frame And Grate Municipal Standard	10	EA	\$1,200.00	\$12,000.00
223	Frame And Grate (or cover) -Removed And Reset	10	EA	\$350.00	\$3,500.00
224.12	12 Inch Hood (The Eliminator)	10	EA	\$280.00	\$2,800.00
227.4	Masonry Plug	10	EA	\$100.00	\$1,000.00
238.12	12 Inch Ductile Iron Pipe	100	SF	\$80.00	\$8,000.00
241.12	12 Inch Reinforced Concrete Pipe	100	FT	\$48.00	\$4,800.00
252.12	12 Inch Corrugated Plastic (Polyethylene) Pipe	100	FT	\$48.00	\$4,800.00
252.15	15 Inch Corrugated Plastic (Polyethylene) Pipe	100	FT	\$50.00	\$5,000.00
252.18	18 Inch Corrugated Plastic (Polyethylene) Pipe	100	FT	\$59.00	\$5,900.00
302.06	6 Inch Ductile Iron Water Pipe	100	FT	\$58.00	\$5,800.00
309	Ductile Iron Fitting For Water Pipe	300	LB	\$6.00	\$1,800.00
350.06	6 Inch Gate And Gate Box	10	EA	\$1,400.00	\$14,000.00
358	Gate Box - Adjusted	10	EA	\$200.00	\$2,000.00
376.2	Hydrant - Removed And Reset	10	EA	\$900.00	\$9,000.00
376.5	Hydrant - AdJusted	10	EA	\$450.00	\$4,500.00
381	Service Box	10	EA	\$300.00	\$3,000.00
402.13	Dense Graded Crushed Stone (Various)	100	TON	\$33.00	\$3,300.00
404.51	Reclaimed Pavement Borrow Material (Various)	100	TON	\$20.00	\$2,000.00
431.1	High Early Strength Cement Concrete Base Course	100	CY	\$140.00	\$14,000.00
440	Calcium Chloride For Roadway Dust Control	1,000	LB	\$0.40	\$400.00
460.01	Hot Mix Asphalt (Areas 2'-4' Wide)	100	TON	\$170.00	\$17,000.00
464	Bitumen For Tack Coat	100	GAL	\$10.00	\$1,000.00

464.5	Hot Poured Rubberized Asphalt Sealer	1,000	FT	\$3.00	\$3,000.00
472	Hot Mix Asphalt -For Miscellaneous Work	100	TON	\$170.00	\$17,000.00
472.6	Hot Mix Asphalt - For Box Widening	100	TON	\$170.00	\$17,000.00
482.3	Sawing Asphalt Pavement	10,000	FT	\$1.25	\$12,500.00
504	Granite Curb Type VA4 - Straight	1,000	FT	\$29.00	\$29,000.00
504.1	Granite Curb Type VA4 - Curved	1,000	FT	\$36.00	\$36,000.00
510	Granite Edging TYPE SA	1,000	FT	\$20.00	\$20,000.00
514	Granite Curb Inlet - Straight	10	EA	\$320.00	\$3,200.00
515	Granite Curb Inlet - Curved	10	EA	\$400.00	\$4,000.00
520.3	Monolithic Cement Concrete Curb Municipal Standard	1,000	FT	\$12.00	\$12,000.00
580	Curb - Removed And Reset	1,000	FT	\$14.00	\$14,000.00
583	Edging - Removed And Reset	1,000	FT	\$12.00	\$12,000.00
590	Curb - Removed and Stacked	1,000	FT	\$0.50	\$500.00
593	Edging - Removed and Stacked	1,000	FT	\$0.50	\$500.00
690	Stone Masonry Wall - Removed And Rebuilt In Cement Mortar	25	CY	\$650.00	\$16,250.00
690.1	Stone Masonry Wall - Removed And Rebuilt Dry	25	CY	\$500.00	\$12,500.00
695	Cement Concrete Block Retaining Wall	1,000	SF	\$35.00	\$35,000.00
697	Sedimentation Fence	100	FT	\$3.50	\$350.00
697.1	Silt Sack	100	EA	\$20.00	\$2,000.00
701	Cement Concrete Sidwalk	2,000	SY	\$49.00	\$98,000.00
701.1	Cement Concrete Sidwalk At Driveways	500	SY	\$63.00	\$31,500.00
701.2	Cement Concrete Wheelchair Ramp	500	SY	\$80.00	\$40,000.00
701.3	Cement Concrete Panel (Less Than 250 SF)	500	SY	\$80.00	\$40,000.00
702	Hot Mix Asphalt Walk Surface	100	TON	\$175.00	\$17,500.00
703	Hot Mix Asphalt Driveway	100	TON	\$175.00	\$17,500.00
704	Stone Dust Walks	10	TON	\$70.00	\$700.00
704.1	Stone Dust For Driveways	10	TON	\$70.00	\$700.00
706	Brick Walk on Hot Mix Asphalt Setting Bed	100	SY	\$200.00	\$20,000.00
706.1	Brick Walk - Removed And Relaid	10	SY	\$125.00	\$1,250.00
751	Loam Barrow	250	CY	\$35.00	\$8,750.00
765	Seeding	2,000	SY	\$2.25	\$4,500.00
767.12	Compost Filter Tube	1,000	FT	\$4.00	\$4,000.00
767.6	Aged Pine Bark Mulch	25	CY	\$80.00	\$2,000.00
767.8	Bales of Hay For Erosion Control	25	EA	\$20.00	\$500.00
767.9	Matting for Erosion Control	25	SY	\$8.00	\$200.00
832	Warning - Regulatory and Route Marker - Alum. Panel (Type A)	50	SF	\$15.00	\$750.00
847.1	Sign Sup (n/Guide)+Rte Mkr W/1 Brkway Post Assembly - Steel	10	EA	\$120.00	\$1,200.00
854.01	Temporary Pavement Markings - 4IN (Painted)	1,000	FT	\$0.65	\$650.00
856.12	Portable Changeable Message Sign	10	WK	\$160.00	\$1,600.00
859	Reflectorized Drum	1,000	DAY	\$0.50	\$500.00
874	Street Name Sign	10	EA	\$125.00	\$1,250.00
875.1	Parking Meter - Removed and Reset	10	EA	\$250.00	\$2,500.00
983.25	Riprap (Including Filter Fabric)	100	SY	\$40.00	\$4,000.00
983.35	Riprap -Removed and Relaid (Including Filter Fabric)	100	SY	\$30.00	\$3,000.00
				TOTAL	\$929,950.00